_____

_____

_____

_____

Date : _____

Manager,
Sungai Tong Palm Oil Mill,
TDM Plantation Sdn. Bhd.
Setiu, Terengganu.

Sir,

RE: SUPPLY, FABRICATE, INSTALLATION, TESTING AND COMMISSIONING PH (POST-HEATED) COOKER FOR 60 MT/HR MILL'S CAPACITY AT SUNGAI TONG PALM OIL MILL, SETIU, TERENGGANU.

ITEM	DESCRIPTIONS	QTY	RATE (RM/Unit)	PRICE (RM)
1.0	**GENERAL AND PRELIMINARIES:** a) To prepare all preliminaries items listed below : i. Contractor all risk and third-party liability insurance. ii. Worker's workmen compensations insurances. iii. Performance bond 5% out of contract value. iv. Contract agreement stamping. v. Mobilization and demobilization. vi. Housekeeping. b) To provide : i. Details photo during work progress / progress report and to be attached together when issuance DO/Invoice. ii. Details Drawing on equipments & machineries layout including electrical works. iii. Testing and Commissioning.			
	Total Item 1.0			

ITEM	DESCRIPTION	QTY	RATE (RM/Unit)	PRICE (RM)
2.0	**EARTHWORKS AND CIVIL WORKS:** 2.1 Hacking Existing Foundation (remove materials from site) 2.2 FFB Conveyors Footings 2.3 PH Cooker Foundation 2.4 Cable Trench			
	Total Item 2.0			
3.0	**STEEL STRUCTURE AND ROOFING:** 3.1 Raise Up PH Cooker Station Building 3 bays by +4m			
	Total Item 3.0			
4.0	**MECHANICAL WORKS:** 4.1 New Thresher Bottom Cross Conveyor, Size Ø700 x 17.5mL 4.2 New Fruit Elevating Conveyor To PH Cooker Size 1000W x 19.5mL c/w Maintenance platform & supports. 4.3 2 units PH Cooker (10,000L per unit) (*CBI design)* 4.4 PH Cooker maintenance Platform & Crane Beam c/w Maintenance Gantry wheel 4.5 2 units PH Discharge Metering Conveyor with level controller 4.6 New fruit elevating conveyor to press station size 1000w x 33.5ml c/w maintenance platform & support 4.7 New top fruit cross conveyor,size Ø700 x 13ml 4.8 PH Condensate Oil Buffer Tank 4.9 PH Condensate Oil Pumps	**2** **2**		
	Total Item 4.0			
5.0	**PIPING, VALVES & INSULATION WORK** 5.1 PH cooker station steam & oil pipeline			
	Total Item 5.0			

ITEM	DESCRIPTION	QTY	RATE (RM/Unit)	PRICE (RM)
6.0	**ELECTRICAL WORKS** 6.1 To supply and installation of the following MCC : *6.1.1* 00A MCC for PH cooker system *6.1.2* DB for PH cooker system area 6.2 To supply install of submain cable from existing MSB (Including modification of existing MSB for new breaker) to new PH cooker system MCC located at existing CS MCC building c/w cable tray, support system, glands,terminations and accessories. 6.3 To supply and installation of all power cables from new MCC 1(Located MCC room) c/w cable tray,support system,glands,terminations and all accessories to all related machines/equipment. 6.4 To supply and installation of all control cable as per following : *6.4.1* LCP c/w Emergency stop *6.4.2* Limit switch *6.4.3* PH cookers system *6.4.4* Control cable between new MCC and existing CS MCC for interlocking 6.5 To supply and installation of flood light and fluorescent light for PH cooker system area 6.6 To supply and installation of earthing system for new MCC (earthing shall be below 1 ohm,new earthing shall be connected with existing earthing system to avoid any potential different between both earth system) 6.7 To supply manpower,tools,cable and all related accessories to modify the existing sterilizer with new PH cooker system 6.8 To supply and installation of new PLC system for the PH cooker system.			
	Total Item 6.0			

ITEM	DESCRIPTIONS	QTY	RATE (RM/Unit)	PRICE (RM)
7.0	**OTHERS** Item not indicated in the specifications or drawing but required for the complete the installation and operation. .... **Remarks :** Contractor is responsible for the housekeeping at the working and surrounding area & to liaise with mill's management for further details. Interested contractors are required to attend a **COMPULSARY** site visit at Sungai Tong Palm Oil Mill, Setiu, Terengganu before submitting their completed quotation and proposal documents. Contractor **MUST** submit together with the **Proposal Construction's Details Drawings.**			
	TOTAL PRICE (RM)			

Amount in words:

_____

_____

_____

Completion Period:_____ weeks

NAME: _____ CHOP/STAMP:

ADDRESS: _____

_____

_____ SIGNATURE: